
# Hyper-K Instrumentation Highlights

RCCN, ICRR, University of Tokyo
II EU Workshop on Water Cherenkov Experiments
for Precision Physics
2025 September 19th




# From Kamiokande to Super-K, and Hyper-K FD

### 45 years legacy of underground water Cherenkov detectors at Kamioka mine

- Factor 2 scale-up, one-order larger FV masses than Super-K
- Basic technology is same, but many new challenges in Hyper-K construction

1983-1996

Kamiokande 3kt / FV 1kt 1000 20"-PMTs



Super-Kamiokande 50kt/ FV 22.5kt 11,000 20"-PMTs)

SK-Gd (2020-)

2028-68m¢


Hyper-Kamiokande (FD) 260kt / FV 186 kt


260kt / FV 186 kt 20,000 20"-PMT + 800 mPMTs


### Many years of consideration until the final design...

• 30mp Donuts rings (M. Koshiba, Phys. Rep. 220 (1992) 229)


K.Nakamura and M.Shiozawa, NooN2000

















### "Word-largest" cavern

### New Challenge in Hyper-K Far Detector instrumentation

A new 50cm-PMT with doubled PDE and pressure tolerance



**Underwater electronics** 



mPMT with 19 3"PMTs



Gd-loading not at the initial phase.
Screening all the material for future capability


**Detector integration** 

# Excavation of Hyper-K cavern

(c) Kamioka Observatory, ICRR, The University of Tokyo




Oct 2023 Dome excavation completed



June 2025 Entire cavern completed


# The single cavern with the largest span ever



H. Tanaka

# A key of the HK cavern excavation


- Information-oriented design and excavation
  - More than 200 monitoring devices installed in the cavern and continuous monitoring of bedrock behavior
    - Ensure the stability of the cavern and safety in the excavation work
    - If an anomaly is detected by the monitoring devices, additional bedrock support and safety measures were implemented
  - The geological model for the cavern stability analysis is continuously updated based on various geological information obtained during the progress of excavation work, e.g., geological inspection, borehole camera data, drilling energy, etc.
  - By integrating all of these information, the bedrock support design and excavation procedures are continuously optimized





### A new 50cm Box-Line PMT (R12860HQE)

- High QE / CE Box-Line type PMT (x2 Super-K PMT)
- Reduction of dark rate (<4kHz in water)</li>
- Improved charge/timing resolution
  - $\Delta T$  7.3ns  $\rightarrow$  4.1 ns, 1PE  $\sigma$ /mean : 53%  $\rightarrow$  35%
- High water pressure tolerance
  - Key to realize the 70-m depths of tank
  - Ensure no damage up to 1.25 MPa (0.6 MPa : Super-K PMT)











### Improvement of water pressure tolerance





Test with a pressure vessel




### Anti-implosion PMT covers to prevent chain reaction

Super-K PMT implosion accident (11th Nov 2001)

Reduce water flow speed

 $(^{\sim}1 \text{ ms} \rightarrow ^{\sim}1 \text{ s})$ 






Promoted by Spanish institutes







### **Hyper-K cover:**





### Underwater implosion test of PMT covers



- Test under the deep sea, Spain Majorca
  - Submerge 3×3 PMT frame
  - Crash PMT at 80m depth
- Sensors monitored pressure waves
- Visual taken by high-speed camera
- ✓ Cover survived after PMT implosion inside
- √ 1/100 shockwave reduction confirmed

#### tourmaline sensor in front of center PMT






### Electronics in HK

- Far detector electronics will be submerged in water
  - Reduction in cable lengths (better signal integrity, less weight)
  - Stringent requirements on reliability (20 years of operation, no serviceability)
  - System to feed nitrogen into vessels (prevent vacuum due to operation in degassed water)
- Modular system
  - High voltage supply (redundant control)
  - Fully redundant low voltage supply
  - Digitizers (T/Q + Time over Threshold)  $\sigma_{\text{time}} \approx 0.25 \text{ ns}, \ \sigma_{\text{q}} \approx 0.16 \text{ pC} \ (\text{at 1 PE} = 19 \text{ pC})$
  - Data processing card (clock recovery, buffering, slow control)
- Timing system and DAQ on tank top
- Prototypes complete, performance confirmed, testing pre-production versions
- Starting final production



#### **Timing distribution system**

- Two-stage system
- GPS/GNSS + atomic clock (redundant)
- Achieved clock jitter
   ≈0.5 ps
- Far & near site beam spill timing via GPS/GNSS time stamping







2-nd stage (TDM)




## Underwater pressure vessel








### Underwater electronics vessels assembly & test @ CERN NP08



Electronic boards contained in a water-tight vessel at pressures up to 8 bars. (Similar vessel for mPMT electronics; MCC)






√560 Pure ID: 24x 20" PMTs

√320 Hybrid for both ID+OD detectors: 20x 20" PMTs + 12x 3" PMTs

Extensively tested in water at CERN and in Japan for several months for stability of humidity, temperature, etc.








High pressure test in water (10 bar) for every vessel and for a fraction of the assembled units

### mPMTs in Hyper-K

mPMT: 19 3" PMTs and electronics arranged inside a pressure resistant vessel



LED-mPMT: 5 PMTs replaced with LED



#### 808 mPMTs for the Hyper-K FD

- Italy: 300 mPMTs

- Poland: 300 mPMTs

- Canada: 200 LED-mPMT

400 mPMTs for IWCD



#### Common R&D but:

#### FD mPMT different from IWCD mPMT:


- Withstand pressure → robust backplate, POM-C cylinder
- Low radioactive contamination
- <u>Different (slower, low power) electronics</u>


#### LED-mPMT

- Mechanics: same as FD mPMT except for PMT support
- Electronics: same as FD mPMT

# Other instrumentation highlights; LINAC / OD

Providing precise absolute energy calibration in 3-24 MeV (5-16 MeV @ Super-K LINAC)







Hyper-K OD: 1-m OD layer w/3" PMT + WLB

(Super-K OD: 2-m OD layer w/ 8" PMT + WLB)

# Hyper-K PMT/Electronics installation


Mockup test (May 2024)








	Top + Bottom	Barrel
ID 20" PMT	6456	13,248
mPMT	256	552
OD 3"PMT	1,076	2,484
Elec. Vessels	290	594
MCC (MPMT)	72	32




92

# Hyper-K FD PMT installation



576 20"IDs + 108 3"ODs + 24 mPMTs + 29 vessels / 4H ring



### Super-K 1st construction/barrel installation (1995)




- 17 3x4-super modules stacked in a vertical tower, and lifted up
- One tower/day
- repeat 38 days → Complete.



For Hyper-K, a ring of 4x288 columns installed in 3-days, because of "interleaving" of cabling






- 1 electronics vessel failure → 24 dead channels
- Prevent concentration of dead channels

### **HK FD construction timeline**

- June 2025: Cavern construction completed.
- August 2025 July 2026: Tank lining construction.
- Jan 2027: Top, Mar-June 2027: Barrel, July-Oct 2027 Bottom installation.
- Nov 2027-June 2028: Water filling → June 2028 Operation starts!





## Summary

- Hyper-K is based on 45yrs legacy of underground water Cherenkov technology.
  - Scale-up by x2 of Super-K in a dimension for 1-order larger FV.
- Not a simple scale-up, while new technical challenges in instrumentation.
  - Cavern: "World-largest" span. Information-oriented design and excavation.
  - New 50cm-PMT: double the PDE, pressure tolerance, and resolution.
  - New PMT covers:
  - mPMT: 19 of 3" PMTs based on KM3Net legacy. Photon direction information.
  - <u>Underwarter electronics:</u> Reduction of PMT cables. Long term stability and lifetime. Underwater vessel and feed-through against the pressure.
  - <u>Detector Integration:</u> One-year installation of 20K 50cmPMTs and multiple components.
- Installation work will start in one-year. Operation foreseen in 3 years.